

## DPX™ 125

MCCBs from 16 to 125 A  
thermal magnetic



250 18



250 59



Dimensions (p. 65)

Electrical characteristics (p. 72-73)

MCCBs for switching, control isolation and protection of low voltage electrical lines

Can be fitted with control and signalling auxiliaries

Can be used with earth leakage modules (opposite) or with residual current relays (p. 63)

Supplied complete with:

- cage terminals

- terminal shields

Conform to IEC 60947-2

Fixed version

Thermal release adjustable from 0.7 to 1 In

Fixed magnetic at 10 In in factory (p. 71)

Thermal adjustment sealable

### DPX-E 125

Pack	Cat.Nos		
	1 P		Breaking capacity Icu: 16 kA (230 V~)
1	250 00		In
1	250 01		16 A
1	250 02		20 A
1	250 03		25 A
1	250 04		32 A
1	250 05		40 A
1	250 06		50 A
1	250 07		63 A
1	250 08		80 A
1	250 09		100 A
1	250 09		125 A
	3 P   4 P		Breaking capacity Icu: 16 kA (400 V~)
1	250 16	250 24	In
1	250 17	250 25	16 A
1	250 18	250 26	25 A
1	250 19	250 27	40 A
1	250 20	250 28	63 A
1	250 21	250 29	100 A
1	250 21	250 29	125 A
1	3 P + N/2		In
1	250 23		125 A

### DPX 125

	3 P   4 P		Breaking capacity Icu: 25 kA (400 V~)
1	250 36	250 44	In
1	250 37	250 45	16 A
1	250 38	250 46	25 A
1	250 39	250 47	40 A
1	250 40	250 48	63 A
1	250 41	250 49	100 A
1	250 41	250 49	125 A
1	3 P + N/2		In
1	250 43		125 A
	3 P   4 P		Breaking capacity Icu: 36 kA (400 V~)
1	250 50	250 58	In
1	250 51	250 59	16 A
1	250 52	250 60	25 A
1	250 53	250 61	40 A
1	250 54	250 62	63 A
1	250 55	250 63	100 A
1	250 55	250 63	125 A
1	3 P + N/2		In
1	250 57		125 A

## DPX™ 125

electronic earth leakage modules  
motor operators



250 45 + 260 13

### Electronic earth leakage modules

Can be fitted directly onto DPX/DPX-I 125

230 V - 500 V~

Adjustable, sealable sensitivity:

0.03 - 0.3 - 1 - 3 A

Adjustable, sealable tripping:

0 - 0.3 - 1 - 3 s

Equipped with:

• test push-button

• reset push-button

Remote earth fault signalling contact  
Switch for mechanical tests on operation and insulation of the device (installation insulation test)

#### Mounted side by side

In

63 A

125 A

#### Mounted underneath

63 A

125 A

Pack	Cat.Nos	
	3 P	4 P
1	260 02	260 03
1	260 12	260 13
1		260 04
1		260 14

### Motor operators

For remote making and breaking of a DPX

circuit and reset in the even of tripping

on a fault

A lock prevents operation when working

on the line

Front operated 24 V=

Front operated 230 V~/=

1	261 00
1	261 03